AABC Commissioning Group AIA Provider Number: 50111116



Commissioning in the Real World: A Case Study

Course Number: CXENERGY1508

Melvin Hidayat, P.E., LEED AP, CEM,

Operations Manager, BPS/BAU Energy Services Siemens Industry April 30, 2015



Credit(s) earned on completion of this course will be reported to AIA CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request. This course is registered with AIA CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.



Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.

Copyright Materials

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of the speaker is prohibited.

SIEMENS

© Siemens 2015



Course Description

This presentation will explore how commissioning strategies meet real world challenges. Learn about the good, the bad and the ugly of a recent project at the HP headquarters building in Palo Alto, CA.

This project involved commissioning select equipment serving over 490,000 square feet of conditioned office space in an expedited timeframe of 5 weeks. The results were improved system performance and identification over 300,000 kWh/year and 20,000 Therms/year in potential energy savings from diagnosis and remediation of inaccurate sensors, mechanical failures, and controls issues.



Learning Objectives

At the end of the this course, participants will be able to:

- 1. Tailor common commissioning practices and strategies to meet real world challenges.
- 2. Understand how commissioning strategies can be used to enhance system performance and increase energy efficiency.
- 3. Learn to diagnose inaccurate sensors, mechanical failures and controls issues.
- 4. Understand the steps necessary to remedy building performance shortcomings stemming from faulty building sensors, mechanical systems and controls.



HP Building 20

Key Building Characteristics:

- > Approximately 490,000 SF over 4 levels (A, B, C and D).
- A 37,700 SF, annex was added in 2013, the Executive Briefing Center and new front lobby for the Headquarter Building.
- Key Systems included: (23) Air Handling Units, (1) AC Unit, (3) Chillers,
 (2) Cooling Towers, and (4) Boilers.
- Primary Function is office space and showcase for executive customers.





HP Building 20





Source: Image taken from Google Earth, March 2015

Goals for the Existing Building Commissioning at B20

Project Goal

- Complete all assessment, investigation and implement approved corrective actions by *April 30, 2014*.
- Support the target of reducing GHG emissions to 20 percent below 2005 levels. (Energy use accounts for 98 percent of the greenhouse gas (GHG) emissions generated by operations at HP.)
- Identify corrective actions and measures through the project.
- Achieve a simple payback of 2.5 years for the overall project through energy improvement measures executed during the project.
- Review and document HVAC systems performance

Challenges:

Work Within the Customer's Expedited Timeline

> Support Sustainability Target

Find and Achieve Energy Savings

> Document Performance



Challenge No. 1: Time is not on our side





Project Development Timeline



Scope of Work for 5 Week Duration

- Verify (79) Critical HVAC Control Sensors
- Repair/Replace Faulty Sensors as found in Investigation
- Verify Current SOO's with Existing Controls Programming
- Confirm Current Facility Requirements
- Functionally Test Major HVAC Systems
- Investigate a Representative Sample (20%) of VAV boxes
- Recommend Corrective Actions and Measures for Found Issues
- Execute Approved Corrective Actions and Measures

Primany Work Tanka & Integration		March			April				Мау			
Primary Work Tasks & Integration		W2	W3	W4	W1	W2	W3	W4	W1	W2	WЗ	W4
B20 Existing Building Commissioning Process Kick-Off												
Establish Communication Plan, Weekly Meeting Structure and Cx Plan												
Gather trend data and equipment information				(
Sensor Verification, Pre-Functional Test Review, VAV Box Testing												
Document Current SOO and Current Facility Requirements						(
Functional Performance Testing and Issue Review						(
Execution of Corrective Actions and Measures								•				
Final System Performance Verification								(
Report Submital - Substantial Completion								(•			
Report Submittal - Final with Comments									1			1
												N N

HP Bldg 20 - Project Schedule



Plan the Process



Key Take Aways:

- Identify and address all resource needs
- Identify critical path tasks and potential risks
- Obtain early commitment of other involved parties
- Be clear and direct in communication
- Set up a workflow that has a bias to action
- Gather you data and information as early as possible

Primany Work Tasks & Integration		March			April				May			
Primary Work Tasks & Integration		₩2	W3	₩4	W1	₩2	WЗ	W4	W1	W2	W3	₩4
B20 Existing Building Commissioning Process Kick-Off												
Establish Communication Plan, Weekly Meeting Structure and Cx Plan				(
Gather trend data and equipment information												
Sensor Verification, Pre-Functional Test Review, VAV Box Testing					()						
Document Current SOO and Current Facility Requirements						(
Functional Performance Testing and Issue Review						(
Execution of Corrective Actions and Measures								•				
Final System Performance Verification								1				
Report Submital - Substantial Completion		1						(
Report Submittal - Final with Comments)	14

HP Bldg 20 - Project Schedule

Project Budget Breakdown

- Approximately 62% of the project budget was allocated to the Commissioning Activities of Planning, Assessment, Investigation and Verification.
- The remaining 38% was set aside for the implementation budget, to perform low cost corrective actions and measures.
- Low cost corrective actions and measure included replacing faulty sensors, VAV box zone controllers, minor repair to mechanical devices (i.e. dampers and linkages).





Communication and Collaboration

- Stipulated in the proposal that access would be readily available.
- Weekly Status Meetings were established with the focus of making decisions at the meetings.
- A communication document was created early on and roles/ responsibilities were discussed.



- Parties involved in the process:
 - Commissioning Agent
 - Site Manager
 - Chief Building Engineer
 - Corporate Real Estate Project Manager
 - Facility Management Company Representative
 - Corporate Sr. Mechanical Engineer
 - Sr. Controls Technician (<u>dedicated for duration of project</u>)
 - Calibration Services Team



Bias towards Action



Informed Advisors:

Facility Management Company Representative Corporate Sr. Mechanical Engineer



Fast Track Workflow





Challenge No. 2: Reduce GHG Emissions through Energy Savings





*Additional, significant Scope 3 emission sources exist beyond the examples provided.

Energy Profile of Building 20

Building Energy Performance Scorecard Your Energy Use Intensity 1 kBtu/SF-Yr 70 Market Average EUI 81 kBtu/SF-Yr Elect: Energy Rate \Rightarrow \$0.100 \$/kWh Gas: Energy Rate 🕹 \$1.25 \$/Therm Elect: Peak to Base 44% Ratio Gas: Peak to Base 🔶 14% Ratio Elect: Weather Correlation 🕹 0.191 R² Value Gas: Weather Correlation $\Rightarrow 0.562$ R² Value Month-Year Peak Electricity Month (kWh) Jul-13 Peak Demand Month (kW) Nov-12 Month-Year Feb-13 Month-Year Peak Gas Month (Gas)

Siemens Energy Services (Nor-Cal Area Team, MH 06/28/13)









*Estimated from CEUS 2006 data

Focused Investigation

- Given the Fast Track nature of the project where do we start?
- > What systems have the largest impact on energy consumption?
- What systems or areas are most prone to failure?
- What devices drive the systems?

Follow the Money...eh..Energy!







Sensors: Critical Point of Failure

- This outside air sensor, located in an alcove is the reference for (14) of the (23) air handling units in the building.
- This sensors was found to 6 degrees off from the calibrate reference reading.





Sensors: (DasttbututerifyVerify

- This was a new combination sensor was used in the annex area. (Installed in 2013)
- > This sensors was found to **4 degrees off** from the calibrated reference reading.







Chiller Lead/Lag Staging

- The Building Chief commented that the CH-1 stays on when switching over to CH-2 or CH-3
- The Chiller Capacities: CH-1: 450-Ton, CH-2: 600-Ton, and CH-3: 800-Ton







Broken Damper Linkage

- > This broken linkage was on the air handling unit serving an executive area.
- > First clue was inspecting the fan room and seeing the VFD at full speed.
- This area cannot be readily access and therefore this issue went undiscovered for a period of time.





Challenge No. 3: Document System Performance

BUILDING 20 B - PALO ALTO.

D

tim asked that t

and dema

of largered critical control compe

Kic

Hp

Scopeorv

a. Strategic Energy Plan Existing Rullding

> and gi Compliance Su Provide (1) Provide spec

Provide



with HP's corpora

of the proje

Key Documentation Tasks

- Utility Data Analysis (Performance Baseline)
- Current Facility Requirements (CFR)
- Current Sequence of Operations (SOO)
- Functional Performance Test (FPT) of Specific HVAC Equipment
- Issues Log
- Recommended Commissioning Corrective Action and Measures (CCA/CCM)







Determining Current Sequence of Operations

Turn This...

(Raw BAS Code)

```
00992
       C
           -----SET UP THE NAME OF THE MECHANICAL SYSTEM------
00994
           REPLACE WITH MECHANICAL SYSTEM.
00996
       C
00998
       C
01000
      DEFINE(X, "B20.AHU-1.")
01005
      DEFINE (Y, "HP.B20AnX.AHU-")
01094
       "B20.PXCC01.BATTERY" = $BATT
01096 C -----USER DEFINED LOCAL POINTS------
01098 C
01100 LOCAL (MADRMP, COOLON, COLOFF, MADRCT, MADCTL, MATCTL, MAD, MOAD, ECONDB, SPFRMP, RNFRMP)
01110 LOCAL (RMTPG, RMTIG)
01120 LOCAL (BSPPG, BSPIG, BSP100, BSS100)
01130
       LOCAL (OCFPG, OCFIG, OCF10, OCS10, MAM)
01140
       "B20.AHU-1.SMOKE" = "B20.AHU-1.SSD"
01194 C
01196 C -----RESET TIMERS / COUNTERS------
01198 C
01200
       SAMPLE (5) IF ("%Y%1.SF.VFD:RUN.STOP CMD" .EQ. ON) THEN "$MADRMP" = "$MADRMP" + 5 ELSE SET (0.0, "$M
       SAMPLE(5) IF("%Y%1.SF.VFD:RUN.STOP CMD" .EQ. ON) THEN "$SPFRMP" = "$SPFRMP" + 5 ELSE SET(0.0,"$S
01210
       SAMPLE(5) IF("%Y%1.RF.VFD:RUN.STOP CMD" .EQ. ON) THEN "$RNFRMP" = "$RNFRMP" + 5 ELSE SET(0.0, "$R
01220
01244
       С
01246 C
                  -----CALCULATE AIR VOLUME FROM VELOCITY PRESSURE AND DUCT AREA-----
01248
      C
      "B20.AHU-1.OCF" = ("B20.AHU-1.OA.VP") * 4.37
01250
01260 C
01270 C CALCULATE KW LOADING OF THE FANS
01280
       "HP.B20AnX.AHU-1.SF.KW" = ("$Y$1.SF.VFD:CURRENT" * "$Y$1.SF.VFD:OUTPUT VOLT")/1000
        "HP.B20AnX.AHU-1.RF.KW" = ("$Y$1.RF.VFD:CURRENT" * "$Y$1.RF.VFD:OUTPUT VOLT")/1000
01285
01290
       C 35 x 18 / 144 4.37
                                 2.91 x 1.5 4.37
                                                     was 25
01292
       C -----SETUP THE RANGES FOR THE CONTROL VALVES & DAMPERS------
01294
      C REPLACE ???CLS AND ???OPN WITH THE MINIMUM
01296 C AND MAXIMUM SIGNALS FOR THE DEVICES.
01298 C
01300 TABLE ("B20.AHU-1.CCO", "B20.AHU-1.CCV", 0, 0, 100, 100)
01310
      TABLE ("B20.AHU-1.HCO", "B20.AHU-1.HCV", 0, 0, 100, 100)
01320
      TABLE ("B20.AHU-1.MAO", "B20.AHU-1.MAD", 0, 0, 100, 100)
01330 TABLE("B20.AHU-1.SVO", "%Y%1.SF.VFD:INPUT REF 1", 0, 0, 100, 80)
01340 TABLE("B20.AHU-1.RVO", "%Y%1.RF.VFD:INPUT REF 1", 0, 0, 100, 100)
01390
       C
01202
       0
```

...Into This

Air Handling Unit Sequence of Operations

The following sequence of operations was proposed, reviewed and installed as part of the Siemens EBCx Pilot Project at B20. (as of 06/05/14)

This sequence applies to: B20 EBC AHU-1

Occupied Mode: When system is in occupied mode, turn on the supply and return/exhaust fans.

Unoccupied Mode:

When the system is unoccupied mode the following shall occur. The supply and return/exhaust fans shall turn off, the mixed air damper shall open to 100%, the outside air damper shall close to 0%, and the cooling and heating controls valve shall close to 0%.

Economizer Mode:

Decision Logic: System shall switch over to Economizer Mode if the outside air temperature drops below the return air temperature. When the outside air temperature rises above the return air temperature + 2°F then Economizer Mode shall be turned OFF.

Economizer Mode ON:

When in Economizer Mode, the mixed air damper shall modulate so that the mixed air temperature set point is maintained.

Economizer Mode OFF:

When Economizer Mode is OFF, the mixed air damper shall be commanded to minimum damper position.

Temperature Control:

Cooling Control Valve Logic: As the supply air temperature loopout value varies between 55 and 100, the cooling control valve shall modulate between 0% and 100% open.

Heating Control Valve Logic:

As the supply air temperature loopout value varies between 45 and 0, the heating control valve shall modulate between 0% and 100% open.

Deadband:

When the supply air temperature looput value varies between 45 and 55, both the cooling and heating control values shall be closed.

Logic Table:

SAT Loopout	CCV (% Open)	HCV (% Open)
100	100	0
55	0	0
45	0	0
0	0	100



Rinse and Repeat

- Even though there were (23) individual air handling units in the building there were only (5) unique applications.
- Therefore once the functional test form was optimized on one air handling unit it could be used on all others with the same application.







Challenge No. 4: Utility Cost Savings (Achieve 2.5 Yr SPB)





Anticipated Energy Savings

Based on the building's energy profile and documented consumption over the last 24 months it was conservatively estimated that the corrective actions and measures would save...

420,000 kWh/yr and 11,000 Therms/yr which equates to approximately *\$52,000/year.*



Sources of Savings

- Air Handling Unit Schedule Optimization
- Economizer Repairs
- Replacing Inaccurate, Mis-located or Faulty Sensors
- Chiller Staging Optimization
- Air Handling Unit Pre-Heat Lockout Adjustment
- After Hours Space Temperature Setback
- Supply Air Temperature Reset

Energy Impacting Commissioning Corrective Actions/Measures

	Electricity	Natural Gas	Elect. Cost	Nat. Gas Cost	Energy Cost
Energy Impacting CCA/CCMs:	(kWh/yr)	(Therms/yr)	(\$/yr)	(Therms/yr)	(\$/yr)
Schedule Optimization	59,659	7,510	\$5,709.35	\$7,833.33	\$13,542.68
Supply Air Temperature Reset	75,244	3,585	\$7,200.84	\$3,738.78	\$10,939.62
Chiller Staging Optimization	31,425		\$3,007.37		\$3,007.37
AH-05 (B Level) Economizer Repair	43,114		\$4,126.02		\$4,126.02
AH-04 (EBC) Economizer Repair	2,819		\$269.82		\$269.82
AH-12 (D Level) Economizer Repair	5,005	1,027	\$479.02	\$1,071.07	\$1,550.09
After hours Schedule Setback	57,936	5,958	\$5,544.47	\$6,213.90	\$11,758.38
OAT sensor repair (B20_OAT)	26,036	3,232	\$2,491.65	\$3,370.97	\$5,862.62
OAT sensor repair (B20.AHU-1.OAT)	-73	97	-\$6.97	\$101.34	\$94.37
Static Pressure Reset	30,728	1,783	\$2,940.70	\$1,860.02	\$4,800.72
HW Pump Lockout Adjustment	4,594		\$439.62		\$439.62
Totals	336,488	23,192	\$ 32,202	\$ 24,189	\$ 56,391

Hewlett Packard Palo Alto B20: Energy End Use Profile (kBtu)





Results

- > All items in the Scope of Work were able to be completed
- Year over Year energy consumption (As of Dec 2014) was reduced by over 940,000 kWh and 17,000 resulting in over \$96,000/yr in savings



- > (79) Sensors were verified, (21) sensors were replaced
- ➤ (4) Failed VAV Box Controllers were replaced
- > (2) Outside air damper linkages were repaired
- > (1) Critical Outside Air Temperature Sensor was relocated
- The following corrective/optimization measures or actions were taken:
 - AHU Schedule Optimization
 - Supply air temperature reset for select AHU's
 - After hours scheduled setback for select AHU's
 - Pre-heat lockout adjustment
 - Economizer controls were optimized for the AHU's
 - Chiller Staging was adjusted
- All systems reviewed (AHU's, CH's, CT's, and Boilers) had their Sequence of Operations documented.



Key Take Aways

- Firm commitments up front to the process and objective by all involved parties.
- Spending extra time planning saves time in the long run. On a fast track project you will probably not have time to make major planning adjustments.
- Verify your sources of information human, electronic or otherwise.
- Spend as much time as possible with the Building Engineers, their knowledge is invaluable.
- Prep as much as possible offsite because once you're on site it is easy to be led off course.





Questions?





This concludes The American Institute of Architects Continuing Education Systems Course

SIEMENS

Mel Hidayat, PE, LEED AP, CEM Operations Manager BPS/BAU Energy Services

mel.hidayat@siemens.com

