



The Evolution of Commissioning at the University of Texas at Austin $\sqrt{2}$

Course Number: CXENERGY1821

Adam Keeling, PE University of Texas John Bixler, PE, LEED AP Alex Gonzales, PE, CxA, LEED AP Jessica Duenez NV5



April 26, 2018

Credit(s) earned on completion of this course will be reported to AIA CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request. for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.

This course is registered with AIA CES



Copyright Materials

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of the speaker is prohibited.





The University of Texas at Austin Utilities and Energy Management



Course Description

An examination of the needs of an institutional client, and the gap left by the traditional new building commissioning process. The University of Texas has been working to transform the requirements of their Commissioning Providers to more robustly support their building operations and optimization while continuing to deliver quality construction projects. Changes include more involvement in the turnover process, a stronger focus on the warranty period, and bringing additional expertise to the table.



Learning Objectives

At the end of the this course, participants will be able to:

1. Understand the needs of institutional clients and the shortfalls of the Initial Commissioning Process from the perspective of an institutional client.

2. Learn about value-added methods for increasing Commissioning Authority (CxA) involvement in the warranty process. Understand the possible CxA scope items in a warranty phase / post occupancy commissioning process.

3. Understand the alignment of LEED V4, the ongoing Monitoring Based Commissioning (MBCx) process, and the requirements of an institutional client.

4. Learn about "Measurement & Verification" results from successful post-occupancy Commissioning project at University of Texas Austin.




WHAT DO INSTITUTIONAL CLIENTS WANT?

From Capital Project Quality Perspective:

- Owners' O&M requirements to be clearly understood
- Clear commissioning process milestones integrated into the project delivery process
- Project delivery team accountability for performance
- Commissioned systems (not just equipment) that will be maintainable, reliable and energy efficient
- "Initial Commissioning" process from design through warranty phase to confirm the Owner's performance (and design) requirements have been met BEFORE project delivery team is released.
- An improved handover of project documentation including commissioning records
- Post Construction "Ongoing Commissioning" support as building load comes on and operators continue to learn building

COMMISSIONING GOALS

- Deliver buildings that meet Owner needs
- Improve equipment performance and mitigate/avoid accelerated deterioration & premature failures
- Improve occupant comfort and productivity
- Optimize energy performance by maximizing efficiency in system performance
- Timely turnover of commissioning documentation
- More effective building operators



- Design/Construction
- Operations/Years 1 25
- Operations/Years 26 40



COMMISSIONING BENEFITS

- Cost avoidance through early identification and resolution of issues
- Energy and life cycle operational costs savings
- Correct controls and building systems operation
- Maintainable building systems
- Increased performance
- Increased equipment life
- Reduced warranty call-backs





WHY IS COMMISSIONING NEEDED?

- Building Performance Matters Now More than Ever
- More Complex and Powerful Systems
- Tests Programming for Energy Efficiency
- Long Term Performance of the Facility
- Identifies Unfinished MEPF Systems
- Completes Building Turnover
- Accreditation Requirements (i.e. JCAHO, Tier 4 Data Center, LEEDV4 O&M)



COMMISSIONING PHASES/PROCESSES

New Construction Commissioning • Review OPR and BOD Cx Plan Cx Specifications Program and Design Reviews Design • Installation/Startup/ TAB/ Controls • SRCs/ FPTs/ IST Construction / • Issue Resolution/ Comprehensive Documentation Acceptance Testing • Functional performance verification; Issue Resolution Supplemental O&M Training, Re-Cx Recommendations Warranty Confirm Systems Operations Supplemental O&M Training • Re-Cx Recommendations and Support Post Warranty

Existing Building Commissioning



WARRANTY PHASE CX TASKS

- Trend Analysis (control related over extended period of time)
- Deferred Testing (due to calendar, seasonal or other requirements – if required)
- Modified Procedures (10-month meeting with Owner, operators, engineer... and incorporate as required)
- Re-commissioning Manual (provides a procedure for continuous or future Cx of the facility)
- Monitoring Based Commissioning









COMMISSIONING CLOSE-OUT ACTIVITIES

- Project Close-Out (Transitioning from Contractor to Owner Facility Operation)
- Ensuring a Successful Training Program
- Transfer of Knowledge and Meaningful Systems Documentation
 - Final Commissioning Report
 - O&M Data/Manuals
 - TAB Report verification
 - Systems Manual
- Documented Baseline Operations
- Ensuring Accurate CMMS/BIM Data for Implementation



- Design/Construction
- Operations/Years 1 25
- Operations/Years 26 40

Incomplete functional testing results and delayed Cx Final Reports and Systems Manual





Phased substantial completions that affect Systems level commissioning completion


Substantial Completion				
Substantial Completion				
1	Passenger Elevators 1-4 Various Corridors and Rooms Throughout Building (See attached Map)	8/10/2017		
2	Café Café Exterior Seating ECJ Level 1	8/17/2017		
3	Exterior Skin East Terrace Skylight Roof Various Corridors and Rooms Throughout Building (See attached Map)	8/29/2017		
4	Service Elevator 1 Various Corridors and Rooms Throughout Building (See attached Map)	9/7/2017		
5	Various Corridors, Rooms, and Site Locations Throughout the Project (See attached Map)	9/14/2017		
6	Various Corridors, Rooms, and Site Locations Throughout the Project (See attached Map)	9/28/2017		



In complete training (not all completed and not all systems ready for training use)


Spec Section Sub Title Subcontractor/ Training Training Hel							
Section	Section		Supplier	Scheduled	training train		
22 1123	2.01.A	PLUMBING EQUIPMENT - Semi-Instantaneous Hot Water Generator - Owner Traning	PORTER		9/6/17 - AM		
26 0573	3.03	FAULT & COORDINATION STUDY & ARC FLASH HAZARD ANALYSIS - Vendor provided Arc Flash Training	WALKER		Complete		
10 4410	3.5.B.1	SMOKE CURTAINS - Owner Training	US SMOKE & FIRE				
14 2123	1.13.B	ELECTRIC PASSENGER ELEVATORS - Owner Training	EMR				
144200	3.4.A	WHEELCHAIR LIFTS - Owner Training	EMR				
23 0801	1.3.1.9	COMMISSIONING OF DIRECT DIGITAL CONTROL SYSTEM - Owner Staff Training	STEMENS				
23 0923.A	2.26.	AIR QUALITY MONITORING - Training (Each Year for 4 Years) At Manufacturer's Factory - Owner Request taining to occur on site at EERG.	STEMENS				
23 0923.A	2.26.	SMOKE PURGE - Training	SIEMENS				
23 0923.A	1.09.A	DIRECT DIGITAL CONTROL SYSTEMS - Owner Training	SIEMENS				
		DIGITAL WAYFINDING SIGNAGE - Owner Training	WALKER				
27 4116	3.7.A	DIGITAL ROOM SCHEDULER - Owner Training	WALKER				
28 3111	3.11.A	DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEMS - Owner Training	WALKER				
27 0800	1.4.1	COMMISSIONING OF COMMUNICATIONS SYSTEMS - Owner Training	WALKER				
27 4116	3.7.A	AUDIOVISUAL SYSTEMS - Owner Training	WALKER				
					<u> </u>		

Building Loading is typically gradual



Building Operators suffering from "Fire Hose" effect





LEEDV4 FUNDAMENTAL & ENHANCED CX

V4 LEED Fundamental - CxA

Independent from Design & Construction

Report directly to Owner – engaged before DD

Reviews OPR & BOD - OPR to cover building envelope envelope

Commissioning Plan

Commissioning in Contract Documents

Verify Installation and Performance

Review results of testing

Final commissioning report

Minimum One Design Review prior to mid-design

Review exterior enclosure design – by A/E SME

Prepare a CFR and O&M Plan

Minimum Systems

Commissioned

- HVAC&R & Controls
- Lighting & Daylighting Controls
- Domestic Hot Water Systems
- Renewable Energy Systems

V4 LEED Enhanced Path 1 - 3 points

Design Review

Review Submittals Concurrent

Confirm Systems Manual Req in CDs

Develop Systems Manual

Verify Training & Reqs in CDs

10th Month Warranty

Develop an on-going commissioning plan plan

LEEDV4 ENHANCED CX OPTIONS



V4 LEED Enhanced: Path 2 Option 1

Achieve Path 1 Enhance Commissioning 3 pts

AND

Develop monitoring-based procedures and include in the commissioning plan **1 pt**

- Measurement requirements
- Points to be tracked
- Limits of acceptable values
- Action plan for identifying and correcting correcting errors and deficiencies
- Training to prevent errors
- Planning for repairs needed to maintain performance
- Frequency of analyses in the 1st year or operation (at least quarterly)
- Update Systems Manual with any mods


V4 LEED Enhanced: Path 2 Option 2

Envelope Commissioning 2 pts

Complete the Cx process activities per ASHRAE ASHRAE Guideline 0-2005 and NIBS Guideline 3 Guideline 3 - 2012

- Review contractor submittals
- Confirm system manual reqs in CDs
- Verify training reqs in CDs
- Verify Systems Manual updates and delivery delivery
- Verify operator and occupant training
- Verify Seasonal testing
- 10th Month Warranty
- Develop an on-going commissioning plan plan

MBCX AND FAULT DETECTION DIAGNOSIS




UT AUSTIN CAMPUS AND POWER PLANT OVERVIEW

- 20+ million square feet of building space
- Variety of building uses
- Age range from 100 years old to brand new
- Combined heat & power plant and chilling stations providing
 - Chilled Water
 - -Steam
 - Electricity



DEMAND-SIDE ENERGY MANAGEMENT & OPTIMIZATION

- Mission and Goal
 - Utilize innovative demand side energy management strategies
 - Offset projected campus energy growth
 - Reduce the average EUI on main campus by at least 2% annually
 - Prevent expansion of plant caused by peak demands



MAIN CAMPUS CONSTRUCTION TRENDS


NV5.COM | Delivering Solutions – Improving Lives

HOW?

- Existing Buildings
 - Existing Building Commissioning (EBCx)
 - Optimize sequences of operation
 - Scheduling
 - Reduce ventilation to meet ASHRAE requirements
 - Replace failed or inefficient equipment
 - Identify maintenance needs with an energy impact
 - Continuous energy use monitoring
 - Component replacement (e.g. lighting, valves, tstats)
- Behavior Programs
 - Longhorn Lights Out
 - Horns Up Sash Down
- New Construction
 - New construction and renovation standards updates
 - Design review for new buildings and large




Target EUIs






TARGET EUIS FOR NEW CONSTRUCTION

- Realistic yet aggressive
 - Energy model prior to 100% CD Phase
 - 10 months after substantial completion
- Based on campus buildings built between the years of 1990-2014
- Benchmarked against
 - Existing energy models for campus buildings
 - Analysis of performance of LEED Silver buildings
 - Labs 21 benchmarking
 - CBECS 2012 averages
 - (Look higher than CBECS because using district energy)



MAP OF AUSTIN'S HEALTH DISTRICT




- 🖉 Health District
 - Dell Medical School Buildings
 - Health District Buildings




HEALTH LEARNING BUILDING CASE STUDY

- Collaboration focus
- State of the Art Technology
- Team based learning classrooms
- Café and Courtyard
- Student Lounges and Conference Rooms
- Simulation Labs
- Anatomy Lab
- Executive and Administration Offices

As the heart of the Dell Medical School and front door for the Medical District, the Health Learning Building is the primary home for students and faculty. But it isn't just a place where things happen — it's a place that makes things happen.





TARGET EUI FOR HEALTH LEARNING BUILDING





EUI CALCULATION FOR NEW BUILDING

Key Question: When did building start normal operation?










ONGOING COMMISSIONING RESULTS



	Chilled Water	Electricity	Hot Water	Total Building
Target EUI	71	29	26	126
Pre Cx	109	30	46	185
Post Cx	90	28	25	143
Avoided mmbtu	1,724	156	1,836	3,716
Avoided %	18%	6%	46%	23%

HEALTH LEARNING BUILDING CASE STUDY

- Evaluated programmed sequences of operations and current building behavior
- Developed 27 recommendations to improve system interactions and overall efficiency
- Facilitated meeting between the EOR, CM, Controls Contractor, Utilities & Energy Management Group to review recommendations.
- Tested the implemented recommendations to verify proper functionality.
- Analyzed trend data to verify systems improvements.
- Re-evaluated trend data on a monthly basis to further fine tune the building.




DISCHARGE AIR TEMPERATURE RESET


- Existing Condition: Reset Based on Linear Relationship with OAT
- Recommendation: Reset Based on Building Demand
- Implementation: Reset Based on Cooling Request
 - Cooling Request = Room Temperature > Cooling Set Point + 1° F
 - Cooling Request > 3 then Reset Temperature Down
 - Cooling Request = 0 then Reset Temperature Up

HEAT RECOVERY PUMP

- Existing Condition: AHU-03 HRP Enable/Disable
 48°F < OAT >78°F
- Colder Return Air Temperature
 from Anatomy Lab
- Implementation: Enable HRP OAT>EAT and OAT-EAT>=5°F




MAKE UP AIR UNIT



- Existing Condition: Preheat Temperature Set Point = 53 F
- Unit Discharges @55 F


MAKE UP AIR UNIT AND AIR HANDLER INTERACTION

- MAT Mid to High 60's
- Simultaneous Heating and Cooling
- Implementation: PHDAT Set Point for MAU-01 = 50°F



STATIC PRESSURE RESET


Rooms Can Change Purpose







ONGOING COMMISSIONING RESULTS



	Chilled Water	Electricity	Hot Water	Total Building
Target EUI	71	29	26	126
Pre Cx	109	30	46	185
Post Cx	90	28	25	143
Avoided mmbtu	1,724	156	1,836	3,716
Avoided %	18%	6%	46%	23%

Learning Objectives

At the end of the this course, participants will be able to:

1. Understand the needs of institutional clients and the shortfalls of the Initial Commissioning Process from the perspective of an institutional client.

2. Learn about value-added methods for increasing Commissioning Authority (CxA) involvement in the warranty process. Understand the possible CxA scope items in a warranty phase / post occupancy commissioning process.

3. Understand the alignment of LEED V4, the ongoing Monitoring Based Commissioning (MBCx) process, and the requirements of an institutional client.

4. Learn about "Measurement & Verification" results from successful post-occupancy Commissioning project at University of Texas Austin.



This concludes The American Institute of Architects Continuing Education Systems Course

Adam Keeling

Alex Gonzales

John Bixler

Jessica Duenez



